


FEHR GRAHAM

ENGINEERING & ENVIRONMENTAL

**Iowa Green Streets Pilot Project
West Union, Iowa**


**Turkey River Watershed Management
Authority**

June 27th, 2013




Project Timeline

- Central business district reconstruction
- First cost estimate prepared in 2004
- Original concept for Standard Type Construction – PCC Street and Sidewalk – storm sewer system
- \$4.5 million estimated construction cost was deemed unaffordable by City – on hold until 2008
- Green Pilot designation by State of Iowa, one of two communities in State – design and financial assistance, plus general project support



Project Timeline


- Visioning meeting took place in June, 2008 – brainstorming session for any and all project concepts – permeable pavers, geothermal district heating and cooling, deicing system, back-in angle parking, totem pole in center of intersection!!
- Storm water management was a priority.
- Not all items stuck! District heating and cooling system did. Deicing and totem pole did not.
- Grant writing started in late 2008, design in 2009
- Secured grants to allow project to be constructed, 2009-2010



Project Timeline

- Bid letting in July 2010.
- Started construction in October 2010.
- Project Completion in June 2013.

Final Project Extents



- 3,000 LF of Street Reconstruction
- 6,000 LF of Sidewalk Reconstruction
- 4,000 LF of New Water Main
- 1,500 LF of New Sanitary Sewer Main
- District Geothermal Heating/Cooling
- 132 Vertical Wells – Courthouse Square
- 7,500 LF of New Geo. Distribution Lines
- LED Street Lighting
- 30,000+ tons of crushed stone

Project Goals

- Replace failing infrastructure in a sustainable way
- Storm water as a resource vs. nuisance
- Energy efficiency
- Improve accessibility - pedestrian friendly
- Local craftsmanship

Project Goals - Storm Water

- Significantly reduce peak runoff rate
- Infiltrate storm water
- Cleanse runoff – filtering effect of crushed stone base
- Cleanse runoff – bioretention - vegetation
- Cool runoff – summer – discharges to trout stream
- Reduce storm drainage infrastructure
- Improved winter performance – reduced sanding

Funding

- \$10,000,000 project
- 15 grants, funding \$7,500,000
- \$2,500,000 City funding


Funding Sources - Grants

- Iowa Great Places - 2009 and 2010
- IDOT - RISE
- CDBG
- Watershed Improvement Review Board (WIRB)
- IDALS - IJOBS
- IJOBS
- IDNR - IJOBS
- Main Street - IJOBS
- Main Street - Challenge
- EPA Climate Showcase
- Department of Energy
- Keep Iowa Beautiful
- Trees Forever - Alliant Energy

Funding Sources - Non Grant

- Fayette County
- Main Street West Union
- Revenue Bonds - Water and Sanitary Sewer
- General Obligation Bond

Original Brick Placement - 1914



- Flint pavers – mfg. near Des Moines
- Pavers placed on 1.5” sand setting bed over 8” concrete
- Many of laborers from Austria
- Residents of West Union helped haul pavers from railroad

- Asphalt overlay of bricks in 1962 – all bricks in place at start of project
- Reused a portion in new project as a historic tie-in

PREPARING AND HAND BRICKING the streets of West Union around 1914. Work was done by Sweeney Brothers.

Pre-Project Conditions



- Asphalt Over Original Brick
- Steep Cross Slopes
- Minimal Storm Sewer System



Pre-Project Storm Water Runoff Downtown West Union




High runoff – especially at downstream ends of central business district

Pre-Project Winter Conditions



Permeable Pavement: Infiltration (Retention) and Detention Capacity



Surfacing Removal



Utility Placement



Excavation Complete



Fabric and Geogrid Placement



Stone Base Profile



Grading - Stone Base Placement



Finish Grading Prior to Setting Bed Placement



Paver Placement



Palletized Pavers

Mechanical Paver Placement



Joint Fill Placement



Coal Vaults Under Sidewalks



Previous Blocked in Basement Openings



Sidewalk Grading - Liner



Sediment Control During Construction



Crushed Stone Check Dams

Sediment Berm With Inlet & Crushed Stone Filter



Bioretention Construction



Finished Bioretention



No More Painting!



High Contrast (White) Pavers Cut In for Parking Stripes and Accessibility Symbols



Paver Infiltration - 350 gpm



Project Results - Storm Water

- Significantly reduce peak runoff rate – successful
- Infiltrate storm water – not so much
- Cleanse runoff – filtering effect of crushed stone base – analysis this year
- Cleanse runoff – bioretention - vegetation – successful
- Cool runoff – successful, analysis this year
- Reduce storm drainage infrastructure – successful
- Improved winter performance – reduced sanding tradeoffs

Finished Project



Additional Storm Water Management - Green Roof



- Chamber of Commerce building
- Tray system
- Required minor structural reinforcement
- Reduces runoff
- Low maintenance
- Increased insulation

Permeable Paver Private Parking



Contact: Jon Biederman
jbiederman@fehr-graham.com

FEHR GRAHAM

ENGINEERING & ENVIRONMENTAL

Insight ■ Experience ■ Results

www.fehr-graham.com